

April 20, 2016

Public Works Facility

Jefferson County

ADDENDUM #4

BIDS DUE: THURSDAY, APRIL 21, 2016 AT 2:00 CDT at the Jefferson County Administration Department, 311 S. Center Ave. RM 111 Jefferson, WI. At that time Bids will be opened publicly for consideration by the Owner.

To all Contract Bidders of record.

This Addendum is issued to modify, explain or correct the original Drawings and Specifications as noted below, and is hereby made a part of the Contract documents. Please attach this Addendum to the Specifications in your possession. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

This Addendum consists of One (1) written page.

QUESTIONS AND ANSWERS

1. Q: *On drawing A-102 the power to gate (future, per add # 2, I believe) is on the south side of the drive. It should be on the North due to the fact that there is not enough room to slide the gate to the South.*
A. Okay to move to north side
2. Q: *In spec sect 32 31 13 page 3 C. Rolling and Man Gates 5. Two man gates as shown on site plan Where? or none required?*
A. Only (3) man gates required
3. Q: *Page 4 Line post spacing: 10 feet on center.... Detail shows 8' o.c.*
A. Spacing to be 8'-0" o.c.
4. Q: *Page 4 C. Brace Assemblies Not needed unless there is no top rail and only a top tension wire.*
A. Correct
5. Q: *Are we adding a 20 amp 2 pole breaker to both locations' panels? The 20 amp 1 pole breaker says Concord but the 2 pole doesn't specify.*
A. Addendum #2 under "Revision to Drawings", Item #2 – The 20A, 2 pole breaker for the well is required at both sites.
6. Q: *A501 shows a drop ceiling in Toilet 101. However E201 doesn't. If it is not, would the fixture need to be changed to a different style like a surface mount 2x4 or a strip fixture ?*
A. There is a drop ceiling@ toilet 101 as shown on detail 12/A-501

* * * * *